MacIntosh & Co. Inc.

Gen Engineering Contractor

CA. Contractors Lic # 951640 sam@macinc.biz

September 9, 2024

City of La Mesa 8152 Commercial La Mesa Ca 91942 Attn: Matt Bell

RE: Collapsed 36" CMP Replacement at Lake Helix

Matt.

We propose to furnish all materials, equipment, labor, and supervision as necessary to complete the work as stated below.

Mobilize site, remove existing fencing to allow access, pot hole existing utilities, remove existing tree stumps thru out work zone and stockpile for disposal, shoot in elevation and slope % from headwall to existing A-5 C/O, excavate down to top of pipe at the outlet headwall and remove section of piping from headwall underneath the existing 8" water line and beyond, clean up excavation, install bedding and grade out for new piping, chip headwall to accept new HDPE piping, install new 36" HDPE pipe into headwall and past the existing 8" water line, sack and patch concrete headwall, place pipe zone bedding up and over new pipe, continue excavation from end of pipe to the existing A-5 C/O, expose existing 30" water line crossing over the SD pipe, remove damaged CMP pipe out from under the water line and out of the A-5 C/O, clean up excavation, install bedding and grade out for new piping, chip existing A-5 C/O to accept new HDPE piping, install new 36" HDPE pipe into the existing A-5 C/O, sack and patch A-5 C/O, place pipe zone bedding up and over new pipe, backfill entire footprint back up to match existing grade, repair existing chain link fence to original and stretch barb wire, load, transport and dispose of demo materials, load, transport and dispose of excess root filled soil, clean up entire site and dress up slopes, demobilize the project

Our total lump sum cost to complete the above stated work is \$75,200.00 including all applicable taxes.

Inclusions

- 1. Equipment necessary to complete the above mentioned scope
- 2. Pothole existing utilities as necessary
- 3. Excavation to expose and replace 36" storm drain piping
- 4. Backfill and compaction
- 5. Sack and patch existing headwall and A-5 C/O Storm Drain Box
- 6. Fuel and consumables
- 7. Remove and replace chain link fence if applicable
- 8. Load, transport and dispose of existing root filled soil and demo marterials
- 9. Final clean entire site
- 10. Mobilization and Demobilization
- 11. Prevailing wage
- 12. Bonds

15871 Sequan Truck Trail Alpine, California 91901 Ph 619- 249-4129

Exclusions

- 1. SWPPP Plan, Implementation of SWPPP's and or development
- 2. Imported soil to balance the site for backfill if necessary
- 3. Pipe bedding or pipe zone bedding
- 4. 36" HDPE pipe, fittings or couplings
- 5. Silt fencing6. Hydro seed
- 7. Encroachment permit and fees
- 8. Traffic control plan or permit fees9. Flaggers or flagging operation
- 10. Shoring / trench plates
- 11. Temp Fencing to secure the site nightly
- 12. Overtime, nights, or weekend work
- 13. Specialty Insurance requirements / GSA / Gaf Con Etc.
- 14. Labor agreements or PLA's
- 15. Dewatering or any work associated with dewatering
- 16. 3rd Party locate
- 17. Unforeseen / Unknowns
- 18. Hazardous material handling, hauling, or encapsulation
- 19. Engineering, engineering calcs
- 20. Survey / staking
- 21. As builds / Cad drawings
- 22. Soils testing
- 23. Concrete cylinder testing

If contracted MCI request this quote to be included in the subcontract.

We sincerely appreciate the opportunity to bid and perform work on your projects.

Sincerely,

Sam MacIntosh MacIntosh & Co. Inc. (619) 249-4129 sam@macinc.biz